SECTION 3

REVIEW PROCESS SUBMITTAL CHECKLIST

This checklist identifies the submittals and meetings set forth in Section 2 of these guidelines, which are required of each lot/parcel owner prior to starting any major construction on Gainey Ranch. In accordance with the Master Architectural Committee rules, the following submittals will be filed with the Master Architectural Committee: 1) preliminary plan review submittal; 2) final plan review submittal; 3) construction set-up submittal. All submittals will include two (2) sets of required plans, indicating name of owner/builder, architect, lot/parcel number, appropriate scale and date of drawing. The owner/builder is also responsible for scheduling two (2) meetings with the Master Architectural Committee: 1) predesign meeting; 2) on site approval meeting at the completion of construction. The following is a detailed checklist about each of these requirements in chronological order. In addition the owner/builder is responsible for scheduling a pre-construction meeting with GRCA management to review the Gainey Ranch Construction Policies.

A. PRE-DESIGN MEETING

Owner, architect and representative of the Master Architectural Committee discuss overall design concept.

B. PRELIMINARY PLAN SUBMITTAL

•	eliminary design must be reviewed and approved prior to preparation of final plans. The tal must include:
	The preliminary Architectural Plans (floor plans, elevations, etc.)
	Site Plan/Master Plan
· ·	Preliminary Landscape Plan (See Section 4, Article II, D)
	Preliminary Project Entry Plan
	Preliminary Plat
	Preliminary Engineering (grading, drainage, utility, paving)
N	Preliminary Wall Layout (perimeter and golf course)
	Other (i.e.: temporary & permanent signage, lighting, model complex, pool/recreation)

C. FINAL PLAN SUBMITTAL

D.

Following the approval of the preliminary design, final plans shall be prepared and submitted. Final Master Architectural Committee approval is required prior to the start of any construction activity. In addition, all plans are to have necessary City of Scottsdale permits and approvals prior to construction.

The following information must be included in the final submittal.
Final Architectural Plans (floor plans, elevations, etc.)
Site Plan/Master Plan
Final Landscape Plan (see Section 4, Article II, D)
Final Project Entry Plan
Final Plat*
Final Engineering* (grading, drainage, utility, paving)
Other (i.e., temporary & permanent signage, lighting, model complex, pool/recreation)
*Requires Professional Certification
DETAILS
Manufacturer's samples, exterior colors, finishes
Sun Control Package - builder/satellite proposed solutions for awnings, trellises, canopies, window treatment
Gutters & Downspouts
Equipment Screening
Mailbox Design
Trash Enclosure/Pick-up
Other

CONSTRUCTION SET-UP SUBMITTAL _____Temporary Construction Office (location, signage, parking, screening, entry) _____Storage Yard (location, screening) _____Overall Project Set-Up (equipment and material storage, deliveries, traffic flow, parking, dust control, access, trash collection) _____Temporary Sales and Marketing Office

F. PRE-CONSTRUCTION MEETING

Other

Owner/builder and representative of Gainey Ranch Community Association discuss construction guidelines and requirements.

G. ON-SITE APPROVAL MEETING

A representative of the Master Architectural Committee meets with the owner or contractor in order to confirm that building conforms to the approved plans at the completion of construction.